CITY OF HARRISBURG 6TH STREET RECONSTRUCT

FROM SMITH STREET TO KESLING STREET

HARRISBURG, OREGON

UTILITY REPRESENTATIVES

ELECTRICAL

PACIFIC POWER HARRISBURG DISTRICT CONTACT: NICOLE WILLIS ALBANY, OR 97322 PHONE: (541) 967-6160 EMAIL: nicole.willis@pacificorp.com

WATER, WASTEWATER, STORM SEWER & CITY FIBER OPTICS

CONTACT: CHUCK SCHOLZ, PUBLIC WORKS DIRECTOR 120 SMITH STREET P.O. BOX 378 HARRISBURG, OR 97446 PHONE: (541) 995-6655

GAS SERVICES

CONTACT: MONTE BROWN 790 GOODPASTURE ISLAND ROAD EUGENE, OR 97401 PHONE: 800-422-4012 X 8338

EMAIL: cscholz@ci.harrisburg.org


COMMUNICATION SERVICES


CENTURY LINK/LUMEN CONTACT: TREVOR GILBERT EUGENE, OR 97401 PHONE: (541) 484-7827 EMAIL: trevor.w.gilbert@lumen.com

CHARTER COMMUNICATIONS CONTACT: MARK STANFIELD PHONE: (541) 201-0097 EMAIL: mark.stanfield@charter.com

CONTACT: SHANE QUIMBY

PHONE: (541) 228-7521 EMAIL: shane.quimby@charter.com





EVERGREEN TREE

WATER IRRIGATION VALVE

HOSE BIB

WATER FOUNTAIN

ABBREVIATIONS

TC TOP OF CURB GL GUTTER LINE CONCRETE AC ASPHALT CONCRETE BW BACK OF WALK HMAC HOT MIX ASPHALT MAX. MAXIMUM

MIN. MINIMUM PSI POUNDS PER SQUARE INCH STA. STATION HWY. HIGHWAY STD. STANDARD DWG DRAWING

W/L WATERLINE EX. EXISTING PROP. PROPOSED SAN SANITARY LAT LATERAL IE INVERT ELEVATION ELEV. ELEVATION FG FINISHED GRADE EG EXISTING GRADE HORZ. HORIZONTAL

ODOT OREGON DEPARTMENT OF TRANSPORTATION PC POINT OF CURVATURE PT POINT OF TANGENCY PVI POINT OF VERTICAL INTERSECTION LVC LENGTH OF VERTICAL INTERSECTION BVCS BEGIN VERTICAL CURVE STATION EVCS END VERTICAL CURVE STATION BVCE BEGIN VERTICAL CURVE ELEVATION EVCE END VERTICAL CURVE ELEVATION PCC POINT OF COMPOUND CURVE PRC POINT OF REVERSE CURVE CL CENTERLINE LEFT

WW WASTEWATER SANITARY SEWER SD STORM DRAIN STM STORM

MH MANHOLE CB CATCH BASIN

DCVA DOUBLE CHECK VALVE ASSEMBLY CI CURB INLET

OWNER

CITY OF HARRISBURG CONTACT: CHUCK SCHOLZ 120 SMITH STREET P.O. BOX 378 PHONE: (541) 995-6655

CIVIL ENGINEER

BRANCH ENGINEERING, INC. CONTACT: DAMIEN GILBERT, P.E. 310 5TH STREET SPRINGFIELD, OR 97477 PHONE: (541) 746-0637

SURVEYOR

BRANCH ENGINEERING CONTACT: DAN NELSON, P.L.S. 310 5TH STREET SPRINGFIELD, OR 97477 PHONE: (541) 746-0637

SITE DATA

SITE ADDRESS HARRISBURG, OR

DISTURBANCE AREA

ELEVATION DATUM ELEVATIONS SHOWN HEREON ARE IN NAVD'88 AS MEASURED BY GPS UNLESS OTHERWISE NOTED.

SHEET #	SHEET TITLE		
C0.0	COVER SHEET		
CO.1	GENERAL NOTES		
C0.2	TYPICAL SECTIONS		
C0.3	TYPICAL SECTIONS		
C1.0	EXISTING CONDITIONS AND DEMO		
C2.0	PROPOSED IMPROVEMENTS		
C2.1	PROPOSED IMPROVEMENTS		
C2.2	CURB RETURN DATA		
C3.0	ADA RAMP DETAILS		
C3.1	ADA RAMP DETAILS		
C3.2	RAISED CROSSWALK DETAILS		
C4.0	STRIPING AND SIGNAGE		
C5.0	DETAILS		
C5.1	DETAILS		
C5.2	DETAILS		
C5.3	DETAILS		
C5.4	DETAILS		
C5.5	DETAILS		
ECO.0	EROSION CONTROL COVER & NOTES		
EC0.1	EROSION CONTROL NOTES		
EC1.0	EROSION CONTROL EXISTING CONDITIONS AND DEMO PLAN		
EC2.0	EROSION CONTROL SITE PLAN		
EC3.0	EROSION CONTROL DETAILS		

VICINITY MAP SCALE: 1"=2000

Springfield, OR 97477 p: 541.746.0637 www.BranchEngineering.com Expires: June 30, 2025

structural • geotechnical SURVEYING

project title:

S

revisions:

MAY 7, 2024 ST/JL

23-009A **COVER SHEET**

GENERAL CONSTRUCTION NOTES

- . CONTRACTOR SHALL PROCURE, AND CONFORM TO ALL CONSTRUCTION PERMITS REQUIRED BY THE CITY OF HARRISBURG, LINN COUNTY AND ODOT
- . ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER. (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 800-332-2334 or 811).
- . CONTRACTOR TO NOTIFY CITY, COUNTY AND ALL UTILITY COMPANIES A MINIMUM OF 48 BUSINESS HOURS (2 BUSINESS DAYS) PRIOR TO START OF CONSTRUCTION. AND COMPLY WITH ALL OTHER NOTIFICATION REQUIREMENTS OF AGENCIES WITH JURISDICTION OVER THE WORK.
- F. CONTRACTOR SHALL PROVIDE ALL BONDS AND INSURANCE REQUIRED BY PUBLIC AND/OR PRIVATE AGENCIES HAVING JURISDICTION. WHERE REQUIRED BY PUBLIC AND/OR PRIVATE AGENCIES HAVING JURISDICTION, THE CONTRACTOR SHALL SUBMIT A SUITABLE MAINTENANCE BOND PRIOR TO FINAL PAYMENT.
- 5. ALL MATERIALS AND WORKMANSHIP FOR FACILITIES IN STREET RIGHT-OF-WAY OR EASEMENTS SHALL CONFORM TO APPROVING AGENCIES' CONSTRUCTION SPECIFICATIONS WHEREIN EACH HAS JURISDICTION, INCLUDING BUT NOT LIMITED TO THE CITY, COUNTY, OREGON HEALTH DIVISION (OHD) AND THE OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ).
- . UNLESS OTHERWISE APPROVED BY THE PUBLIC WORKS DIRECTOR, CONSTRUCTION OF ALL PUBLIC FACILITIES SHALL BE DONE BETWEEN 7:00 A.M. AND 6:00 P.M., MONDAY THROUGH SATURDAY.
- THE CONTRACTOR SHALL PERFORM ALL WORK NECESSARY TO COMPLETE THE PROJECT IN ACCORDANCE WITH THE APPROVED CONSTRUCTION DRAWINGS INCLUDING SUCH INCIDENTALS AS MAY BE NECESSARY TO MEET APPLICABLE AGENCY REQUIREMENTS AND PROVIDE A COMPLETED PROJECT.
- 3. ANY INSPECTION BY THE CITY, COUNTY OR OTHER AGENCIES SHALL NOT, IN ANY WAY, RELIEVE THE CONTRACTOR FROM ANY OBLIGATION TO PERFORM THE WORK IN STRICT COMPLIANCE WITH THE CONTRACT DOCUMENTS, APPLICABLE CODES, AND AGENCY REQUIREMENTS.
- . CONTRACTOR SHALL MAINTAIN ONE COMPLETE SET OF APPROVED DRAWINGS ON THE CONSTRUCTION SITE AT ALL TIMES WHEREON HE WILL RECORD ALL APPROVED DEVIATIONS IN CONSTRUCTION FROM THE APPROVED DRAWINGS. AS WELL AS THE STATION LOCATIONS AND DEPTHS OF ALL EXISTING UTILITIES ENCOUNTERED. THESE FIELD RECORD DRAWINGS SHALL BE KEPT UP TO DATE AT ALL TIMES AND SHALL BE AVAILABLE FOR INSPECTION BY THE CITY OR OWNER'S REPRESENTATIVE UPON REQUEST. FAILURE TO CONFORM TO THIS REQUIREMENT MAY RESULT IN DELAY IN PAYMENT AND/OR FINAL ACCEPTANCE OF THE PROJECT.
- 10.UPON COMPLETION OF CONSTRUCTION OF ALL NEW FACILITIES, CONTRACTOR SHALL SUBMIT A CLEAN SET OF FIELD RECORD DRAWINGS CONTAINING ALL AS—BUILT INFORMATION TO THE ENGINEER. ALL INFORMATION SHOWN ON THE CONTRACTOR'S FIELD RECORD DRAWINGS SHALL BE SUBJECT TO VERIFICATION. IF SIGNIFICANT ERRORS OR DEVIATIONS ARE NOTED, AN AS-BUILT SURVEY PREPARED AND STAMPED BY A REGISTERED PROFESSIONAL LAND SURVEYOR SHALL BE COMPLETED AT THE CONTRACTOR'S EXPENSE.
- 11.CONTRACTOR SHALL CONFORM TO DEQ STORMWATER PERMIT NO. 1200C FOR CONSTRUCTION ACTIVITIES WHERE 1 ACRE OR MORE ARE DISTURBED.
- 12. THE CONTRACTOR SHALL RETAIN AND PAY FOR THE SERVICES OF A REGISTERED CIVIL ENGINEER AND/OR LAND SURVEYOR LICENSED IN THE STATE OF OREGON TO ESTABLISH CONSTRUCTION CONTROL AND PERFORM INITIAL CONSTRUCTION SURVEYS TO ESTABLISH THE LINES AND GRADES OF IMPROVEMENTS AS INDICATED ON THE DRAWINGS. STAKING FOR BUILDINGS, STRUCTURES, CURBS, GRAVITY DRAINAGE PIPES/STRUCTURES AND OTHER CRITICAL IMPROVEMENTS SHALL BE COMPLETED USING EQUIPMENT ACCURATE TO 0.04 FEET HORIZONTALLY AND 0.02 FEET VERTICALLY, OR BETTER. USE OF GPS EQUIPMENT FOR CONSTRUCTION STAKING OF THESE IMPROVEMENTS IS ALLOWED IF USED IN CONJUNCTION WITH THE ESTABLISHED CONSTRUCTION CONTROL MENTIONED ABOVE.
- 13.CONTRACTOR SHALL ERECT AND MAINTAIN BARRICADES, WARNING SIGNS, TRAFFIC CONES PER CITY AND COUNTY REQUIREMENTS IN ACCORDANCE WITH THE MUTCD (INCLUDING OREGON AMENDMENTS). ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES. CONTRACTOR SHALL COORDINATE WITH PROPERTY OWNERS AND/OR RESIDENTS REGARDING ACCESS DURING CONSTRUCTION. ALL TRAFFIC CONTROL MEASURES SHALL BE APPROVED AND IN PLACE PRIOR TO ANY CONSTRUCTION ACTIVITY. PRIOR TO ANY WORK IN THE EXISTING PUBLIC RIGHT-OF-WAY, CONTRACTOR SHALL SUBMIT FINAL TRAFFIC CONTROL PLAN TO THE CITY, COUNTY AND ODOT FOR REVIEW AND ISSUANCE OF A LANE CLOSURE OR WORK IN RIGHT-OF-WAY PERMIT
- 14.THE CONTRACTOR SHALL BE RESPONSIBLE TO ENSURE THAT ALL REQUIRED OR NECESSARY INSPECTIONS ARE COMPLETED BY AUTHORIZED INSPECTORS PRIOR TO PROCEEDING WITH SUBSEQUENT WORK WHICH COVERS OR THAT IS DEPENDENT ON THE WORK TO BE INSPECTED. FAILURE TO OBTAIN NECESSARY INSPECTION(S) AND APPROVAL(S) SHALL RESULT IN THE CONTRACTOR BEING FULLY RESPONSIBLE FOR ALL PROBLEMS ARISING FROM UNINSPECTED WORK.
- 15. UNLESS OTHERWISE SPECIFIED, THE ATTACHED "REQUIRED TESTING AND FREQUENCY" TABLE OUTLINES THE MINIMUM TESTING SCHEDULE FOR THE PROJECT. THIS TESTING SCHEDULE IS NOT COMPLETE, AND DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF OBTAINING ALL NECESSARY INSPECTIONS OR OBSERVATIONS FOR ALL WORK PERFORMED, REGARDLESS OF WHO IS RESPONSIBLE FOR PAYMENT. COST FOR RETESTING SHALL BE BORNE BY THE CONTRACTOR.
- 16. THE LOCATION AND DESCRIPTIONS OF EXISTING UTILITIES SHOWN ON THE DRAWINGS ARE COMPILED FROM AVAILABLE RECORDS AND/OR FIELD SURVEYS. THE ENGINEER OR UTILITY COMPANIES DO NOT GUARANTEE THE ACCURACY OR THE COMPLETENESS OF SUCH RECORDS. CONTRACTOR SHALL FIELD VERIFY LOCATIONS AND SIZES OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.
- 17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND MARKING ALL EXISTING SURVEY MONUMENTS OF RECORD (INCLUDING BUT NOT LIMITED TO PROPERTY AND STREET MONUMENTS) PRIOR TO CONSTRUCTION. IF ANY SURVEY MONUMENTS ARE REMOVED, DISTURBED OR DESTROYED DURING CONSTRUCTION OF THE PROJECT, THE CONTRACTOR SHALL RETAIN AND PAY FOR THE SERVICES OF A REGISTERED PROFESSIONAL SURVEYOR LICENSED IN THE STATE OF OREGON TO REFERENCE AND REPLACE ALL SUCH MONUMENTS PRIOR TO FINAL PAYMENT. THE MONUMENTS SHALL BE REPLACED WITHIN A MAXIMUM OF 90 DAYS, AND THE COUNTY SURVEYOR SHALL BE NOTIFIED IN WRITING AS REQUIRED BY PER ORS 209.150.
- 18.CONTRACTOR SHALL FIELD VERIFY LOCATION AND DEPTH OF ALL EXISTING UTILITIES WHERE NEW FACILITIES CROSS. ALL UTILITY CROSSINGS MARKED OR SHOWN ON THE DRAWINGS SHALL BE POTHOLED USING HAND TOOLS OR OTHER NON BORING METHODS. PRIOR TO EXCAVATING, CONTRACTOR SHALL BE RESPONSIBLE FOR EXPOSING POTENTIAL UTILITY CONFLICTS FAR ENOUGH AHEAD OF CONSTRUCTION TO MAKE NECESSARY GRADE OR ALIGNMENT MODIFICATIONS WITHOUT DELAYING THE WORK. IF GRADE OR ALIGNMENT MODIFICATION IS NECESSARY, CONTRACTOR SHALL NOTIFY THE DESIGN ENGINEER, AND THE DESIGN ENGINEER OR THE OWNER'S REPRESENTATIVE SHALL OBTAIN APPROVAL FROM THE CITY PRIOR TO CONSTRUCTION.
- 19.ALL FACILITIES SHALL BE MAINTAINED IN—PLACE BY THE CONTRACTOR UNLESS OTHERWISE SHOWN OR DIRECTED. CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO SUPPORT, MAINTAIN, OR OTHERWISE PROTECT EXISTING UTILITIES AND OTHER FACILITIES AT ALL TIMES DURING CONSTRUCTION. CONTRACTOR TO LEAVE EXISTING FACILITIES IN AN EQUAL OR BETTER-THAN-ORIGINAL CONDITION AND TO THE SATISFACTION OF THE CITY AND OWNER'S REPRESENTATIVE.

- 20.UTILITIES OR INTERFERING PORTIONS OF UTILITIES THAT ARE ABANDONED IN PLACE SHALL BE REMOVED BY THE CONTRACTOR TO THE EXTENT NECESSARY TO ACCOMPLISH THE WORK. THE CONTRACTOR SHALL PLUG THE REMAINING EXPOSED ENDS OF ABANDONED UTILITIES.
- 21.CONTRACTOR SHALL REMOVE ALL EXISTING SIGNS, MAILBOXES, FENCES, LANDSCAPING, ETC., AS REQUIRED TO AVOID DAMAGE DURING CONSTRUCTION AND REPLACE THEM TO EXISTING OR BETTER CONDITION.
- 22.THE CONTRACTOR SHALL BE RESPONSIBLE FOR MANAGING CONSTRUCTION ACTIVITIES TO ENSURE THAT PUBLIC STREETS AND RIGHT-OF-WAYS ARE KEPT CLEAN OF MUD, AND DUST OR DEBRIS. DUST ABATEMENT SHALL BE MAINTAINED BY ADEQUATE WATERING OF THE SITE BY THE CONTRACTOR.
- 23.FINISH PAVEMENT GRADES AT TRANSITION TO EXISTING PAVEMENT SHALL MATCH EXISTING PAVEMENT GRADES OR BE FEATHERED PAST JOINTS WITH PAVEMENT AS REQUIRED TO PROVIDE A SMOOTH, FREE DRAINING SURFACE.
- 24.ALL EXISTING OR CONSTRUCTED MANHOLES, CLEANOUTS, MONUMENT BOXES, GAS VALVES, WATER VALVES AND SIMILAR STRUCTURES SHALL BE ADJUSTED TO MATCH FINISH GRADE OF THE PAVEMENT, SIDEWALK, LANDSCAPED AREA OR MEDIAN STRIP WHEREIN THEY LIE. VERIFY THAT ALL VALVE BOXES AND RISERS ARE CLEAN AND CENTERED OVER THE OPERATING NUT.
- 25.CONTRACTOR SHALL SEED AND MULCH (UNIFORMLY BY HAND OR HYDROSEED) EXPOSED SLOPES AND DISTURBED AREAS WHICH ARE NOT SCHEDULED TO BE LANDSCAPED, INCLUDING TRENCH RESTORATION AREAS. IF THE CONTRACTOR FAILS TO APPLY SEED AND MULCH IN A TIMELY MANNER DURING PERIODS FAVORABLE FOR GERMINATION, OR IF THE SEEDED AREAS FAIL TO GERMINATE, THE CITY'S REPRESENTATIVE MAY (AT HIS DISCRETION) REQUIRE THE CONTRACTOR TO INSTALL SOD TO COVER SUCH DISTURBED AREAS.
- 26.ALL TAPPING OF EXISTING MUNICIPAL SANITARY SEWER, STORM DRAIN MAINS, AND MANHOLES MUST BE DONE BY CONTRACTOR FORCES.
- 27.THE CONTRACTOR SHALL HAVE APPROPRIATE EQUIPMENT ON SITE TO PRODUCE A FIRM, SMOOTH, UNDISTURBED SUBGRADE AT THE TRENCH BOTTOM, TRUE TO GRADE. THE BOTTOM OF THE TRENCH EXCAVATION SHALL BE SMOOTH, FREE OF LOOSE MATERIALS OR TOOTH GROOVES FOR THE ENTIRE WIDTH OF THE TRENCH PRIOR TO PLACING THE GRANULAR BEDDING MATERIAL.
- 28.ALL PIPES SHALL BE BEDDED WITH MINIMUM 6-INCHES OF 1"-0 CRUSHED ROCK BEDDING AND BACKFILLED WITH COMPACTED 1"-0 CRUSHED ROCK IN THE PIPE ZONE (CRUSHED ROCK SHALL EXTEND A MINIMUM OF 12-INCHES OVER THE TOP OF THE PIPE IN ALL CASES). CRUSHED ROCK OR CDF TRENCH BACKFILL SHALL BE USED UNDER ALL IMPROVED AREAS. INCLUDING PAVEMENT. SIDEWALKS. FOUNDATION SLABS. BUILDINGS. ETC. IN ACCORDANCE WITH THE PLANS & SPECIFICATIONS. GRANULAR TRENCH BACKFILL SHALL BE COMPACTED TO 95% OF THE MAXIMUM DRY DENSITY PER AASHTO T-180 TEST METHOD (MODIFIED PROCTOR).
- 29.GRANULAR TRENCH BEDDING AND BACKFILL SHALL CONFORM TO THE REQUIREMENTS OF OSSC (ODOT/APWA) 02630.10 (DENSE GRADED BASE AGGREGATE), 1"-0. UNLESS OTHERWISE SHOWN ON THE DRAWINGS, COMPACT GRANULAR BACKFILL TO 95% OF THE MAXIMUM DRY DENSITY PER AASHTO T-180 TEST METHOD (MODIFIED PROCTOR).
- 30.ALL PIPED UTILITIES ABANDONED IN PLACE SHALL HAVE ALL OPENINGS CLOSED WITH CONCRETE PLUGS WITH A MINIMUM LENGTH EQUAL TO 2 TIMES THE DIAMETER OF THE ABANDONED PIPE.
- 31.THE END OF ALL UTILITY SERVICE LINES SHALL BE MARKED WITH A 2-X-4 PAINTED WHITE AND WIRED TO PIPE STUB. THE PIPE DEPTH SHALL BE WRITTEN ON THE POST IN 2" BLOCK LETTERS.
- 32.ALL NON-METALLIC WATER, SANITARY AND STORM SEWER PIPING SHALL HAVE AN ELECTRICALLY CONDUCTIVE INSULATED 12 GAUGE COPPER TRACER WIRE THE FULL LENGTH OF THE INSTALLED PIPE USING BLUE WIRE FOR WATER AND GREEN WIRE FOR STORM AND SANITARY PIPING. TRACER WIRE SHALL BE EXTENDED UP INTO ALL VALVE BOXES, CATCH BASINS, MANHOLES AND LATERAL CLEANOUT BOXES. TRACER WIRE PENETRATIONS INTO MANHOLES SHALL BE WITHIN 18 INCHES OF THE RIM ELEVATION AND ADJACENT TO MANHOLE STEPS. THE TRACER WIRE SHALL BE TIED TO THE TOP MANHOLE STEP OR OTHERWISE SUPPORTED TO ALLOW RETRIEVAL FROM THE OUTSIDE OF THE MANHOLE.
- 33.NO TRENCHES IN SIDEWALKS, ROADS, OR DRIVEWAYS SHALL BE LEFT IN AN OPEN CONDITION OVERNIGHT. ALL SUCH TRENCHES SHALL BE CLOSED BEFORE THE END OF EACH WORKDAY AND NORMAL TRAFFIC AND PEDESTRIAN FLOWS RESTORED.
- 34.CITY FORCES TO OPERATE ALL VALVES, INCLUDING FIRE HYDRANTS, ON EXISTING PUBLIC MAINS.
- 35.ALL WATER MAINS AND SANITARY SEWER FORCE MAINS SHALL BE C-900 PVC (DR 18) RESPECTIVELY. ALL FITTINGS 4-INCHES THROUGH 24-INCHES IN DIAMETER SHALL BE DUCTILE IRON FITTINGS IN CONFORMANCE WITH AWWA C-153 OR AWWA C-110. THE MINIMUM WORKING PRESSURE FOR ALL MJ CAST IRON OR DUCTILE IRON FITTINGS 4-INCHES THROUGH 24-INCH IN DIAMETER SHALL BE 350 PSI FOR MJ FITTINGS AND 250 PSI FOR FLANGED FITTINGS.
- 36.ALL WATER MAINS TO BE INSTALLED WITH A MINIMUM 36 INCH COVER TO FINISH GRADE UNLESS OTHERWISE NOTED OR DIRECTED. WATER SERVICE LINES SHALL BE INSTALLED WITH A MINIMUM 30-INCH COVER. DEEPER DEPTHS MAY BE REQUIRED AS SHOWN ON THE DRAWINGS OR TO AVOID OBSTRUCTIONS.
- 37. THRUST RESTRAINT SHALL BE PROVIDED ON ALL BENDS, TEES AND OTHER DIRECTION CHANGES PER LOCAL JURISDICTION REQUIREMENTS AND AS SPECIFIED OR SHOWN ON THE DRAWINGS. UNLESS OTHERWISE SHOWN OR APPROVED BY THE ENGINEER, ALL VALVES SHALL BE FLANGE CONNECTED TO ADJACENT TEES OR CROSSES.
- 38.CONTRACTOR SHALL PROVIDE ALL NECESSARY EQUIPMENT AND MATERIALS (INCLUDING PLUGS, BLOWOFFS, VALVES, SERVICE TAPS, ETC.) REQUIRED TO FLUSH, TEST AND DISINFECT WATERLINES PER PUBLIC AGENCY REQUIREMENTS.
- 39.WHERE SANITARY SEWER LINES CROSS ABOVE OR WITHIN 18-INCHES VERTICAL SEPARATION BELOW A WATERLINE, SEWER MAINS AND/OR SERVICE LATERALS SHALL BE REPLACED WITH A 18-FOOT LENGTH OF CLASS 50 DUCTILE IRON OR C-900 PVC PIPE (DR 18) CENTERED AT THE CROSSING IN ACCORDANCE WITH OAR 333 AND LOCAL JURISDICTION REQUIREMENTS. CONNECT TO EXISTING SEWER LINES WITH APPROVED RUBBER COUPLINGS. EXAMPLE: FOR AN 8-INCH WATERLINE WITH 36-INCHES COVER, 4-INCH SERVICE LATERAL INVERTS WITHIN 5.67-FEET (68-INCHES) OF FINISH GRADE MUST BE DI OR C-900 PVC AT THE CROSSING. CENTER ONE FULL LENGTH OF WATERLINE PIPE AT POINT OF CROSSING THE SEWER LINE OR SEWER LATERAL.
- 40.CONTRACTOR SHALL PROVIDE ALL NECESSARY MATERIALS, EQUIPMENT AND FACILITIES TO TEST. SANITARY SEWER PIPE AND APPURTENANCES FOR LEAKAGE IN ACCORDANCE WITH TESTING SCHEDULE HEREIN OR THE CITY'S CONSTRUCTION STANDARDS, WHICHEVER ARE MORE STRINGENT. SANITARY SEWER PIPE AND APPURTENANCES SHALL BE TESTED FOR LEAKAGE.
- 41.CONTRACTOR SHALL NOTIFY AND COORDINATE WITH FRANCHISE UTILITIES FOR REMOVAL OR RELOCATION OF POWER POLES, VAULTS, PEDESTALS, MANHOLES, ETC. TO AVOID CONFLICT WITH CITY UTILITY STRUCTURES, FIRE HYDRANTS, METERS, SEWER OR STORM LATERALS, ETC.
- 42.CONTRACTOR TO COORDINATE AND NOTIFY WITH ALL PROPERTY OWNERS A MINIMUM OF 48 HOURS IN ADVANCE WHENEVER A CITY'S UTILITY (WATER, SEWER, &/OR STORM) SERVICE WILL BE DISRUPTED FOR ANY AMOUNT OF

REQUIRED TESTING AND FREQUENCY TABLE		PARTY RESPONSIBLE FOR PAYMENT		
		CONTRACTOR	OTHERS (see note 1	
STREETS, PARKING LOTS, PADS, FILLS, ETC				
ASPHALT 1 TEST/6,000 S.F./LIFT (4 MIN.)	Χ	SEE NOTE 2		
PIPED UTILITIES, ALL				
TRENCH BACKFILL 1 TEST/200 FOOT TRENCH/LIFT (4 MIN.)	Х	SEE NOTE 2		
TRENCH AC RESTORATION 1 TEST/300 FOOT OF TRENCH (4 MIN.)	Х	SEE NOTE 2		
WATER				
PRESSURE TEST (TO BE WITNESSED BY OWNER'S REPRESENTATIVE OR APPROVING AGENCY)	X	SEE NOTE 4		
BACTERIAL WATER TESTPER OREGON HEALTH DIVISION	Х	SEE NOTE 2		
CHLORINE RESIDUAL TEST PER CITY REQUIREMENTS	X	SEE NOTE 2		
SANITARY SEWER (GRAVITY)				
PIPE —AIR OR HYDROSTATIC PER ODOT REQUIREMENTS. —DEFLECTION TESTING PER ODOT REQUIREMENTS. —VIDEO INSPECTION PER ODOT REQUIREMENTS.	Х	SEE NOTE 2		
MANHOLES VACUUM TESTING PER ODOT REQUIREMENTS	Х	SEE NOTE 2		
CONCRETE				
SLUMP, AIR & CYLINDERS FOR ALL STRUCTURES CURBS, SIDEWALKS AND PCC PAVEMENTS. UNLESS OTHERWISE SPECIFIED, ONE SET OF CYLINDERS PER 100 CUBIC YARDS (OR PORTION THEREOF) OF CONCRETE POURED PER DAY. SLUMP & AIR TESTS REQUIRED ON SAME LOAD AS CYLINDERS.	X	SEE NOTE 2		


- "OTHERS" REFERS TO CITY'S AUTHORIZED REPRESENTATIVE OF APPROVING AGENCY AS APPLICABLE. CONTRACTOR RESPONSIBLE FOR SCHEDULING TESTING. ALL TESTING MUST BE COMPLETED PRIOR TO PERFORMING SUBSEQUENT
- NOTE 2: TESTING MUST BE PERFORMED BY AN APPROVED INDEPENDENT TESTING LABORATORY OR COMPANY.
- IN ADDITION TO IN-PLACE DENSITY TESTING, THE SUBGRADE AND BASE ROCK SHALL BE PROOF ROLLED WITH A LOADED 10 YARD DUMP TRUCK PROVIDED BY THE CONTRACTOR. BASEROCK PROOFROLL SHALL TAKE PLACE IMMEDIATELY PRIOR TO (WITHIN 24 HOURS OF) PAVING, AND SHALL BE WITNESSED BY THE CITY'S AUTHORIZED REPRESENTATIVE OR APPROVING AGENCY. LOCATION AND PATTERN OF PROOFROLL TO BE DIRECTED BY SAID CITY'S REPRESENTATIVE OR APPROVING AGENCY.
- NOTE 4: TO BE WITNESSED BY THE CITY'S REPRESENTATIVE OR APPROVING AGENCY. THE CONTRACTOR SHALL PERFORM PRE-TESTS PRIOR TO SCHEDULING WATERLINE OR SANITARY SEWER PRESSURE TESTS, OR PIPELINE MANDREL



civil • transportation structural • geotechnical SURVEYING 310 5th Street

www.BranchEngineering.com

Springfield, OR 97477 p: 541.746.0637



project title:

9

STR J MIT S OM 'RRI Ш FR(HA

S

KENSLING

 \vdash 0

Ы U


revisions:

MAY 7, 2024

designer 23-009A

NOTES

ST/JL



Branch **ENGINEERINGE**

> structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477

www.BranchEngineering.com

p: 541.746.0637



project title:

KENSLING


STREET TO I

revisions:

MAY 7, 2024 ST/JL

> 23-009A **TYPICAL SECTIONS**

C0.2



GUTTER PAN SLOPE.

copyright © 2016 Branch Engineering, Inc.

Branch **ENGINEERINGE**

> structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477

> civil • transportation

p: 541.746.0637

www.BranchEngineering.com



project title:

9

STREET

KENSLING

STREET TO I


revisions:

MAY 7, 2024

ST/JL 23-009A

> **TYPICAL SECTIONS**

C0.3



ENGINEERING≝

structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477

civil • transportation

p: 541.746.0637 www.BranchEngineering.com



project title:

KENSLING

STREET TO OREGON

SMITI SBUR

FROM HARRI

ST/JL


revisions:

MAY 7, 2024

drawn by:


23-009A **EXISTING CONDITIONS**


& DEMO



CONSTRUCTION NOTES

- CONTRACTOR TO ADJUST EXISTING WATER VALVE BOX TO PROPOSED FINISHED GRADE PER DETAIL RD258, SHEET C5.4.
- CONTRACTOR TO ADJUST EXISTING WATER METER BOX TO PROPOSED FINISHED GRADE PER DETAIL RD274, SHEET C5.4.
- (300)—CONTRACTOR TO ADJUST EXISTING WASTEWATER MANHOLE TO PROPOSED FINISHED GRADE PER DETAIL RD338, SHEET C5.4.
- 500 RELOCATED LIGHT POLE. COORDINATE WORK WITH PACIFIC POWER (JARAD ALBERS 541-967-6179).
- CONSTRUCT PAVEMENT SECTION, CURB & GUTTER OR STANDARD CURB, AND SIDEWALK PER TYPICAL SECTIONS, SHEET CO.2 & CO.3.
- (602)—CONSTRUCT CONCRETE CURB & GUTTER PER ODOT STD DWG RD700, SHEET C5.1 AND TYPICAL SECTIONS, SHEET CO.2 & CO.3. DRILL 3/4" X 4 1/2" HOLES INTO EXISTING GUTTER BAR AND CURB. FILL HOLES WITH EPOXY AND INSERT 8" LONG #5 REBAR INTO HOLE PRIOR TO POURING NEW CURB & GUTTER.
- 605 CONSTRUCT ADA RAMP INCLUDING TRUNCATED DOMES. PLACE 4" MINIMUM THICKNESS OF 1" MINUS CRUSHED ROCK UNDER 4" THICK CONCRETE ADA RAMPS AND LANDINGS. SEE SHEET C3.1 FOR DETAILS WITH DIMENSIONS AND SPOT ELEVATIONS. REFER TO STD DWG RD902 & RD920, SHEET C5.3.
- 606 CONSTRUCT CONCRETE DRIVEWAY PER ODOT STD DWG RD750 OPTION N, SHEET C5.1. PLACE 6" MINIMUM THICKNESS 1" MINUS CRUSHED ROCK,
- 607 CONSTRUCT CURB ENDING PER ODOT STD DWG RD700, SHEET C5.1.
- 608 CONSTRUCT 6" CONCRETE CURB, VARY EXPOSURE PER GRADE SHOTS ON SHEET
- C3.0 & C3.1 PER ODOT STD DWG RD700, SHEET C5.1.
- SEAL PAVEMENT JOINT. TACK COAT EXISTING PAVEMENT EDGES. THE MATCHLINE TO EXISTING PAVING SHALL COMPLY WITH ODOT STD DWG RD302, SHEET C5.3. 610 - PROTECT EXISTING CONCRETE SIDEWALK AND CONCRETE CURB & GUTTER.
- 611 MATCH EXISTING GRADE.
- 612 INSTALL MAILBOX IN LOCATION SHOWN ON SINGLE SUPPORT OR MULTIPLE SUPPORT PER ODOT STD DWG RD100, SHEET C5.2.
- (615)—REINSTALL FENCE IN LOCATION SHOWN AT BACK OF SIDEWALK.





ENGINEERING

structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477

p: 541.746.0637

civil • transportation

www.BranchEngineering.com



Expires: June 30, 2025


project title:

TREE S KENSLING

revisions:

MAY 7, 2024 ST/JL 23-009A

PROPOSED IMPROVEMENTS



PT: POINT OF TANGENCY

LEFT RIGHT ELEV: ELEVATION

copyright © 2016 Branch Engineering, Inc.

ENGINEERING

structural • geotechnical S U R V E Y I N G

Springfield, OR 97477

p: 541.746.0637 www. Branch Engineering.com



Expires: June 30, 2025

project title:

KENSLING


STREET TO , OREGON


FROM SMITH SHARISBURG,


MAY 7, 2024

drawn by: ST/JL 23-009A

CURB RETURN DATA







ENGINEERING

civil • transportation structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477 p: 541.746.0637

www.BranchEngineering.com



project title:


STREET


KENSLING


revisions:

MAY 7, 2024

23-009A ADA







605 6TH & KESLING - W INTERSECTION
C2.1 SCALE: 1": 5"

civil • transportation structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477 p: 541.746.0637

www.BranchEngineering.com



Expires: June 30, 2025

project title:


KENSLING STREET

revisions:

MAY 7, 2024

23-009A

ADA **DETAILS**






KENSLING STREET

MAY 7, 2024

ST/JL

23-009A





CONSTRUCTION NOTES

- 240 MAINTAIN AND PROTECT EXISTING SIGN.
- RELOCATE EXISTING SIGN ASSEMBLY AND POST TO NEW ANCHOR FOUNDATION PER ODOT STD DWGS TM200, TM681 AND TM687, SHEET C5.2 AT NEW LOCATION SHOWN.
- 242 REMOVE EXISTING SIGN ASSEMBLY.
- PROVIDE AND INSTALL 8" WHITE LINE PER ODOT STD DWG TM500, SHEET C5.5.
- PROVIDE AND INSTALL (S) STANDARD 1'-0" STOP BAR PER ODOT STD DWG TM503, SHEET C5.5.
- PROVIDE AND INSTALL 4" WHITE LINE FOR 18'X8' PULL—IN PARKING PER ODOT STD DWG TM500, SHEET C5.5.
- INSTALL STANDARD CROSSWALK STRIPING AND SIGNING PER DETAIL TM503, SHEET C5.5.
- INSTALL STAGGERED CONTINENTAL CROSSWALK STRIPING AND SIGNING PER DETAIL TM503, SHEET C5.5.
- PROVIDE AND INSTALL (S) STANDARD BIKE LANE STENCIL (WHITE) PER ODOT STD DWG TM503, SHEET C5.5.

ALL STRIPING MATERIALS SHALL COMPLY WITH CURRENT OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION (2024 EDITION OR NEWER) AND SHALL BE INSTALLED PER CURRENT OREGON STANDARD DRAWINGS, MODIFIED AS DESCRIBED HEREIN, WHERE APPLICABLE.

TRANSVERSE MARKINGS AND LEGENDS SHALL BE TYPE B—HS PREFORMED FUSED THERMOPLASTIC FILM HIGH SKID.





Branch

Since 1977
civil • transportation
structural • geotechnical
SURVEYING

310 5th Street Springfield, OR 97477 p: 541.746.0637

www.BranchEngineering.com



project title:

HARRISBURG 6TH STREET
RECONSTRUCT

KENSLING STREET

STREET TO OREGON

SMITH ISBURG,


revisions:

te: MAY 7, 2024 awn by: ST

signer: ST/JL eject no: 23-009A

STRIPING

C40



copyright $\ensuremath{\text{@}}$ 2016 Branch Engineering, Inc.

structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477

p: 541.746.0637 www.BranchEngineering.com

civil • transportation




project title:


RE S KENSLING STREET TO OREGON S SMITH ISBURG, FROM HARRIS


revisions:


MAY 7, 2024

ST/JL designer project no: 23-009A









structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477

civil • transportation

p: 541.746.0637 www.BranchEngineering.com



project title:

ш

S

SNSLING

T TC ON

<u>ن</u> بيا

STREI ORE

SMIT! SBUR


OM \RRI


revisions:


date:


MAY 7, 2024 drawn by:

ST/JL designer project no: 23-009A









civil • transportation structural • geotechnical SURVEYING 310 5th Street

Springfield, OR 97477 p: 541.746.0637

www.BranchEngineering.com



project title:

ш

S


KENSLING T TC STREE OREG SMITH ISBURG, FROM HARRI


revisions:


project no:


MAY 7, 2024 drawn by: ST/JL designer

23-009A









civil • transportation structural • geotechnical SURVEYING 310 5th Street

p: 541.746.0637 www.BranchEngineering.com

Springfield, OR 97477

√ #62780PEプ DIGITALLY SIGNED Expires: June 30, 2025

project title:

ш S SNSLING T TC <u>ں</u> بیا

STRI


SMIT


S


OM \RRI


revisions:

MAY 7, 2024 date: drawn by: ST/JL designer project no: 23-009A









Branch ENGINEERING Since 1977

civil • transportation

S U R V E Y I N G

310 5th Street
Springfield, OR 97477

p: 541.746.0637

www.BranchEngineering.com



oiost titlo:

project title:

oject title.

RISBURG 6TH STREET ONSTRUCT

TRE

S

KENSLING

T TC

STREE OREG

SMIT! ISBUR(

FROM HARRI


revisions:


date: MAY 7, 2024 drawn by: ST


designer: ST/JL project no: 23-009A


DETAILS

C5.4









ENGINEERINGE

civil • transportation

structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477

p: 541.746.0637

www.BranchEngineering.com

REI

S

KENSLING

revisions:

MAY 7, 2024

23-009A

DETAILS

C5.5

BMP MATRIX FOR CONSTRUCTION PHASE

	CLEARING/ DEMO	MASS GRADING/ UTILITY CONSTRUCTION	VERTICAL CONSTRUCTION	FINAL STABILIZATION
CONCRETE TRUCK WASHOUT				
CONSTRUCTION ENTRANCE	X	X		
DEWATERING (TREATMENT LOCATION, SCHEMATIC	^	^		
& SAMPLING PLAN REQUIRED)				
a or time that it but it begins by				
EARTH DIKES (STABILIZED)				
EROSION CONTROL BLANKETS AND MATS				
(SPECIFY TYPE)				
MULCHES (SPECIFY TYPE)				Х
MYCORRHIZAE/BIOFERTILIZERS				
NATURAL BUFFER ZONES				
ORANGE FENCING (PROTECTING				
SENSITIVE/PRESERVED AREAS)				
				X
PERMANENT SEEDING AND PLANTING				X
DDFOFD/F FWOTING MEGETATION	X	X		.,
PRESERVE EXISTING VEGETATION	X	X		X
	X	X		X
	X	X		X
STORM DRAIN INLET PROTECTION				
STRAW WATTLES (OR OTHER MATERIALS)				
TEMPORARY DIVERSION DIKES				
TEMPORARY OR PERMANENT SEDIMENTATION BASINS				
TEMPORARY SEEDING AND PLANTING				
TREATMENT SYSTEM (OPERATION &MAINTENANCE PLAN REQUIRED)				
UNPAVED ROADS GRAVELED OR OTHER BMP ON ROAD				
VEGETATIVE BUFFER STRIPS				

INSPECTION SCHEDULE

	SITE CONDITION	MINIMUM FREQUENCY		
1.	ACTIVE PERIOD	ON INITIAL DATE THAT LAND DISTURBANCE ACTIVITIES COMMENCE. WITHIN 24 HOURS OF ANY STORM EVENT, INCLUDING RUNOFF FROM SNOW MELT, THAT RESULTS IN DISCHARGE FROM THE SITE. AT LEAST ONCE EVERY 14 DAYS, REGARDLESS OF WETHER STORMWATER RUNOFF IS OCCURRING.		
2.	INACTIVE PERIODS GREATER THAN FOURTEEN (14) CONSECUTIVE CALENDAR DAYS	THE INSPECTOR MAY REDUCE THE FREQUENCY OF INSPECTIONS IN ANY AREA OF THE SITE WHERE THE STABILIZATION STEPS IN SECTION 2.2.20 HAVE BEEN COMPLETED TO TWICE PER MONTH FOR THE FIRST MONTH, NO LESS THAN 14 CALENDAR DAYS APART, THEN ONCE PER MONTH.		
3.	PERIODS DURING WHICH THE SITE IS INACCESSIBLE DUE TO INCLEMENT WEATHER	IF SAFE, ACCESSIBLE AND PRACTICAL, INSPECTIONS MUST OCCUR DAILY AT A RELEVANT DISCHARGE POINT OR DOWNSTREAM LOCATION OF THE RECEIVING WATERBODY.		
4.	PERIODS DURING WHICH CONSTRUCTION ACTIVITIES ARE SUSPENDED AND RUNOFF IS UNLIKELY DUE TO FROZEN CONDITIONS.	VISUAL MONITORING INSPECTIONS MAYBE TEMPORARILY SUSPENDED. IMMEDIATELY RESUME MONITORING UPON THAWING, OR WHEN WEATHER CONDITIONS MAKE DISCHARGES LIKELY.		
5.	PERIODS DURING WHICH CONSTRUCTION ACTIVITIES ARE CONDUCTED AND RUNOFF IS UNLIKELY DURING FROZEN CONDITIONS.	VISUAL MONITORING INSPECTIONS MAYBE REDUCED TO ONCE A MONTH. IMMEDIATELY RESUME MONITORING UPON THAWING, OR WHEN WEATHER CONDITIONS MAKE DISCHARGES LIKELY.		

RATIONAL STATEMENT

A COMPREHENSIVE LIST OF AVAILABLE BEST MANAGEMENT PRACTICES (BMP) OPTIONS BASED ON DEQ'S GUIDANCE MANUAL HAS BEEN REVIEWED TO COMPLETE THIS EROSION AND SEDIMENT CONTROL PLAN. SOME OF THE ABOVE LISTED. BMPs WERE NOT CHOSEN BECAUSE THEY WERE DETERMINED TO NOT EFFECTIVELY MANAGE EROSION PREVENTION AND SEDIMENT CONTROL FOR THIS PROJECT BASED ON SPECIFIC SITE CONDITIONS. INCLUDING SOIL CONDITIONS TOPOGRAPHIC CONSTRAINTS. ACCESSIBILITY TO THE SITE. AND OTHER RELATED CONDITIONS. AS THE PROJECT PROGRESSES AND THERE IS A NEED TO REVISE THE ESC PLAN. AN ACTION PLAN WILL BE SUBMITTED

AUTHORIZED NON-STORMWATER DISCHARGES

- WATER AND ASSOCIATED DISCHARGES FROM EMERGENCY FIREFIGHTING ACTIVITIES
- FIRE HYDRANT FLUSHING PROPERLY MANAGED LANDSCAPING IRRIGATION
- 4. WATER USED TO WASH EQUIPMENT AND VEHICLES (EXCLUDING THE ENGINE, UNDERCARRIAGE, AND WHEELS/TIRES) PROVIDED THERE IS NO DISCHARGE OF SOAPS, SOLVENTS, OR DETERGENTS USED
- WATER USED TO CONTROL DUST POTABLE WATER INCLUDING UNCONTAMINATED WATER LINE FLUSHINGS
- EXTERNAL BUILDING WASHDOWN, PROVIDED SOAPS, SOLVENTS, AND DETERGENTS ARE NOT USED, AND EXTERNAL
- SURFACES DO NOT CONTAIN HAZARDOUS SUBSTANCES PAVEMENT WASH WATERS, PROVIDED SPILLS OR LEAKS OF TOXIC OR HAZARDOUS SUBSTANCES HAVE NOT
- OCCURRED (UNLESS ALL SPILL MATERIAL HAS BEEN REMOVED) AND WHERE SOAPS, SOLVENTS, AND DETERGENTS ARE NOT USED. DIRECTING PAVEMENT WASH WATERS INTO ANY SURFACE WATER, STORM DRAIN INLET, OR STORMWATER CONVEYANCE IS PROHIBITED, UNLESS THE CONVEYANCE IS CONNECTED TO A SEDIMENT BASIN, SEDIMENT TRAP, OR SIMILARLY EFFECTIVE CONTROL FOR THE POLLUTANTS PRESENT. PER 2.2.19.b, HOSING OF ACCUMULATED SEDIMENTS ON PAVEMENT INTO ANY STORMWATER CONVEYANCE IS PROHIBITED
- UNCONTAMINATED, NON-TURBID DISCHARGES OF GROUNDWATER OR SPRING WATER 10. FOUNDATION OR FOOTING DRAINS WHERE FLOWS ARE NOT CONTAMINATED WITH PROCESS MATERIALS SUCH AS SOLVENTS OR CONTAMINATED GROUNDWATER
- 11. CONSTRUCTION DEWATERING ACTIVITIES (INCLUDING GROUNDWATER DEWATERING AND WELL DRILLING DISCHARGE ASSOCIATED WITH THE REGISTERED CONSTRUCTION ACTIVITY), PROVIDED THAT:
- a. THE WATER IS LAND APPLIED IN A WAY THAT RESULTS IN COMPLETE INFILTRATION WITH NO POTENTIAL TO DISCHARGE TO A SURFACE WATER OF THE STATE, OR THE USE OF A SANITARY OR COMBINED SEWER
- DISCHARGES AUTHORIZED WITH LOCAL SEWER DISTRICT APPROVAL, OR b. BEST MANAGEMENT PRACTICES AND A TREATMENT SYSTEM APPROVED BY DEQ OR AGENT (SEE SECTION 1.2.9) ARE USED TO ENSURE COMPLIANCE WITH DISCHARGE AND WATER QUALITY REQUIREMENTS IN SECTION 2.4

6TH STREET RECONSTRUCT

CONSTRUCTION SITE MANAGEMENT PLAN HARRISBURG, LINN COUNTY, OREGON

DEQ GENERAL NOTES

- 1. ONCE KNOWN, INCLUDE A LIST OF ALL CONTRACTORS THAT WILL ENGAGE IN CONSTRUCTION ACTIVITIES ON SITE, AND THE AREAS OF THE SITE WHERE THE CONTRACTOR(S) WILL ENGAGE IN CONSTRUCTION ACTIVITIES. REVISE LIST AS APPROPRIATE UNTIL PERMIT COVERAGE IS TERMINATED (SECTION 4.4.c.i). IN ADDITION, INCLUDE A LIST OF ALL PERSONNEL (BY NAME AND POSITION) THAT ARE RESPONSIBLE FOR THE DESIGN, INSTALLATION AND MAINTENANCE OF STORMWATER CONTROL MEASURES (e.g. ESCP DEVELOPER, BMP INSTALLER (SEE SECTION 4.10), AS WELL AS THEIR INDIVIDUAL RESPONSIBILITIES. (SECTION 4.4.c.ii)
- INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS. (SECTION 6.5.Q)

VISUAL MONITORING INSPECTION REPORTS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-C PERMIT REQUIREMENTS. (SECTION 6.5)

- 4. RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ. AGENT. OR THE LOCAL MUNICIPALITY. (SECTION 4.7) THE PERMIT REGISTRANT MUST IMPLEMENT THE ESCP. FAILURE TO IMPLEMENT ANY OF THE CONTROL MEASURES OR PRACTICES DESCRIBED IN THE ESCP IS A VIOLATION OF THE PERMIT. (SECTIONS 4 AND 4.11)
- THE ESCP MUST BE ACCURATE AND REFLECT SITE CONDITIONS. (SECTION 4.8)
- SUBMISSION OF ALL ESCP REVISIONS IS NOT REQUIRED. SUBMITTAL OF THE ESCP REVISIONS IS ONLY UNDER SPECIFIC CONDITIONS. SUBMIT ALL NECESSARY REVISION TO DEQ OR AGENT WITHIN 10 DAYS. (SECTION 4.9) 8. SEQUENCE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL TO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF EROSION. (SECTION 2.2.2)
- CREATE SMOOTH SURFACES BETWEEN SOIL SURFACE AND EROSION AND SEDIMENT CONTROLS TO PREVENT STORMWATER FROM BYPASSING CONTROLS AND PONDING. (SECTION 2.2.3)
- 10. IDENTIFY, MARK, AND PROTECT (BY CONSTRUCTION FENCING OR OTHER MEANS) CRITICAL RIPARIAN AREAS AND VEGETATION INCLUDING IMPORTANT TREES AND ASSOCIATED ROOTING ZONES, AND VEGETATION AREAS TO BE PRESERVED IDENTIFY VEGETATIVE BUFFER ZONES BETWEEN THE SITE AND SENSITIVE AREAS (E.G., WETLANDS), AND OTHER AREAS TO BE PRESERVED, ESPECIALLY IN PERIMETER AREAS, (SECTION 2.2.1) 11. PRESERVE EXISTING VEGETATION WHEN PRACTICAL AND RE-VEGETATE OPEN AREAS. RE-VEGETATE OPEN AREAS WHEN PRACTICABLE BEFORE AND AFTER GRADING OR CONSTRUCTION. IDENTIFY THE TYPE OF VEGETATIVE SEED MIX USED.
- 12. MAINTAIN AND DELINEATE ANY EXISTING NATURAL BUFFER WITHIN THE 50-FEET OF WATERS OF THE STATE. (SECTION 2.2.4)
- 13. INSTALL PERIMETER SEDIMENT CONTROL, INCLUDING STORM DRAIN INLET PROTECTION AS WELL AS ALL SEDIMENT BASINS, TRAPS, AND BARRIERS PRIOR TO LAND DISTURBANCE. (SECTIONS 2.1.3) 14. CONTROL BOTH PEAK FLOW RATES AND TOTAL STORMWATER VOLUME, TO MINIMIZE EROSION AT OUTLETS AND DOWNSTREAM CHANNELS AND STREAMBANKS. (SECTIONS 2.1.1. AND 2.2.16)
- 15. CONTROL SEDIMENT AS NEEDED ALONG THE SITE PERIMETER AND AT ALL OPERATIONAL INTERNAL STORM DRAIN INLETS AT ALL TIMES DURING CONSTRUCTION, BOTH INTERNALLY AND AT THE SITE BOUNDARY. (SECTIONS 2.2.6 AND 2.2.13) 16. ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK. (SECTION 2.2.14) 17. APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS AS GRADING PROGRESSES. TEMPORARY OR PERMANENT STABILIZATIONS MEASURES ARE NOT REQUIRED FOR AREAS THAT ARE
- INTENDED TO BE LEFT UNVEGETATED, SUCH AS DIRT ACCESS ROADS OR UTILITY POLE PADS.(SECTIONS 2.2.20 AND 2.2.21) 18. ESTABLISH MATERIAL AND WASTE STORAGE AREAS, AND OTHER NON-STORMWATER CONTROLS. (SECTION 2.3.7) 19. KEEP WASTE CONTAINER LIDS CLOSED WHEN NOT IN USE AND CLOSE LIDS AT THE END OF THE BUSINESS DAY FOR THOSE CONTAINERS THAT ARE ACTIVELY USED THROUGHOUT THE DAY. FOR WASTE CONTAINERS THAT DO NOT HAVE
- LIDS, PROVIDE EITHER (1) COVER (E.G., A TARP, PLASTIC SHEETING, TEMPORARY ROOF) TO PREVENT EXPOSURE OF WASTES TO PRECIPITATION, OR (2) A SIMILARLY EFFECTIVE MEANS DESIGNED TO PREVENT THE DISCHARGE OF POLLUTANTS (E.G., SECONDARY CONTAINMENT). (SECTION 2.3.7) 20. PREVENT TRACKING OF SEDIMENT ONTO PUBLIC OR PRIVATE ROADS USING BMPS SUCH AS: CONSTRUCTION ENTRANCE, GRAVELED (OR PAVED) EXITS AND PARKING AREAS, GRAVEL ALL UNPAVED ROADS LOCATED ONSITE, OR USE AN EXIT
- TIRE WASH. THESE BMPS MUST BE IN PLACE PRIOR TO LAND- DISTURBING ACTIVITIES. (SECTION 2.2.7)
- 21. WHEN TRUCKING SATURATED SOILS FROM THE SITE, EITHER USE WATER-TIGHT TRUCKS OR DRAIN LOADS ON SITE. (SECTION 2.2.7.F) 22. CONTROL PROHIBITED DISCHARGES FROM LEAVING THE CONSTRUCTION SITE, I.E., CONCRETE WASH-OUT, WASTEWATER FROM CLEANOUT OF STUCCO, PAINT AND CURING COMPOUNDS. (SECTIONS 1.5 AND 2.3.9)
- 23. ENSURE THAT STEEP SLOPE AREAS WHERE CONSTRUCTION ACTIVITIES ARE NOT OCCURRING ARE NOT DISTURBED. (SECTION 2.2.10)
- 24. PREVENT SOIL COMPACTION IN AREAS WHERE POST-CONSTRUCTION INFILTRATION FACILITIES ARE TO BE INSTALLED. (SECTION 2.2.12) 25. USE BMPS TO PREVENT OR MINIMIZE STORMWATER EXPOSURE TO POLLUTANTS FROM SPILLS; VEHICLE AND EQUIPMENT FUELING, MAINTENANCE, AND STORAGE; OTHER CLEANING AND MAINTENANCE ACTIVITIES; AND WASTE HANDLING ACTIVITIES. THESE POLLUTANTS INCLUDE FUEL, HYDRAULIC FLUID, AND OTHER OILS FROM VEHICLES AND MACHINERY, AS WELL AS DEBRIS, FERTILIZER, PESTICIDES AND HERBICIDES, PAINTS, SOLVENTS, CURING COMPOUNDS AND
- ADHESIVES FROM CONSTRUCTION OPERATIONS. (SECTIONS 2.2.15 AND 2.3) 26. PROVIDE PLANS FOR SEDIMENTATION BASINS THAT HAVE BEEN DESIGNED PER SECTION 2.2.17 AND STAMPED BY AN OREGON PROFESSIONAL ENGINEER. (SEE SECTION 2.2.17.A)

6 OTHER SEDIMENT BARRIERS (SLICH AS RIORACS). REMOVE SEDIMENT REFORE IT REACHES TWO INCHES DEPTH AROVE CROLLIND HEIGHT AND REFORE RMP REMOVAL (SECTION 2.1.5.0

- 27. IF ENGINEERED SOILS ARE USED ON SITE, A SEDIMENTATION BASIN/IMPOUNDMENT MUST BE INSTALLED. (SEE SECTIONS 2.2.17 AND 2.2.18)
- 29. IMPLEMENT THE FOLLOWING BMPS WHEN APPLICABLE: WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KITS IN ALL VEHICLES, REGULAR
- MAINTENANCE SCHEDULE FOR VEHICLES AND MACHINERY, MATERIAL DELIVERY AND STORAGE CONTROLS, TRAINING AND SIGNAGE, AND COVERED STORAGE AREAS FOR WASTE AND SUPPLIES. (SECTION 2.3) 30. USE WATER, SOIL-BINDING AGENT OR OTHER DUST CONTROL TECHNIQUE AS NEEDED TO AVOID WIND-BLOWN SOIL. (SECTION 2.2.9)
- 31. THE APPLICATION RATE OF FERTILIZERS USED TO REESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS TO MINIMIZE NUTRIENT RELEASES TO SURFACE WATERS. EXERCISE CAUTION WHEN USING TIME-RELEASE FERTILIZERS WITHIN ANY WATERWAY RIPARIAN ZONE. (SECTION 2.3.5) 32. IF AN ACTIVE TREATMENT SYSTEM (FOR EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED, SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM SCHEMATIC, LOCATION OF SYSTEM, LOCATION OF INLET, LOCATION OF DISCHARGE DISCHARGE DISPERSION DEVICE DESIGN, AND A SAMPLING PLAN AND FREQUENCY) BEFORE OPERATING THE TREATMENT SYSTEM. OBTAIN
- ENVIRONMENTAL MANAGEMENT PLAN APPROVAL FROM DEQ BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS. (SECTION 1.2.9) 33. TEMPORARILY STABILIZE SOILS AT THE END OF THE SHIFT BEFORE HOLIDAYS AND WEEKENDS, IF NEEDED. THE REGISTRANT IS RESPONSIBLE FOR ENSURING THAT SOILS ARE STABLE DURING RAIN EVENTS AT ALL TIMES OF THE YEAR.
- 34. AS NEEDED BASED ON WEATHER CONDITIONS, AT THE END OF EACH WORKDAY SOIL STOCKPILES MUST BE STABILIZED OR COVERED, OR OTHER BMPS MUST BE IMPLEMENTED TO PREVENT DISCHARGES TO SURFACE WATERS OR CONVEYANCE SYSTEMS LEADING TO SURFACE WATERS. (SECTION 2.2.8) 35. SEDIMENT FENCE: REMOVE TRAPPED SEDIMENT BEFORE IT REACHES ONE THIRD OF THE ABOVE GROUND FENCE HEIGHT AND BEFORE FENCE REMOVAL. (SECTION 2.1.5.B)
- 37. CATCH BASINS: CLEAN BEFORE RETENTION CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT. SEDIMENT BASINS AND SEDIMENT TRAPS: REMOVE TRAPPED SEDIMENTS BEFORE DESIGN CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT 38. WITHIN 24 HOURS, SIGNIFICANT SEDIMENT THAT HAS LEFT THE CONSTRUCTION SITE, MUST BE REMEDIATED. INVESTIGATE THE CAUSE OF THE SEDIMENT RELEASE AND IMPLEMENT STEPS TO PREVENT A RECURRENCE OF THE DISCHARGE
- WITHIN THE SAME 24 HOURS. ANY IN-STREAM CLEAN-UP OF SEDIMENT SHALL BE PERFORMED ACCORDING TO THE OREGON DEPARTMENT OF STATE LANDS REQUIRED TIMEFRAME. (SECTION 2.2.19.A) 39. THE INTENTIONAL WASHING OF SEDIMENT INTO STORM SEWERS OR DRAINAGE WAYS MUST NOT OCCUR. VACUUMING OR DRY SWEEPING AND MATERIAL PICKUP MUST BE USED TO CLEANUP RELEASED SEDIMENTS. (SECTION 2.2.19) 40. DOCUMENT ANY PORTION(S) OF THE SITE WHERE LAND DISTURBING ACTIVITIES HAVE PERMANENTLY CEASED OR WILL BE TEMPORARILY INACTIVE FOR 14 OR MORE CALENDAR DAYS. (SECTION 6.5.F.)
- 41. PROVIDE TEMPORARY STABILIZATION FOR THAT PORTION OF THE SITE WHERE CONSTRUCTION ACTIVITIES CEASE FOR 14 DAYS OR MORE WITH A COVERING OF BLOWN STRAW AND A TACKIFIER, LOOSE STRAW, OR AN ADEQUATE COVERING OF COMPOST MULCH UNTIL WORK RESUMES ON THAT PORTION OF THE SITE. (SECTION 2.2.20)
- 42. DO NOT REMOVE TEMPORARY SEDIMENT CONTROL PRACTICES UNTIL PERMANENT VEGETATION OR OTHER COVER OF EXPOSED AREAS IS ESTABLISHED. ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED, ALL TEMPORARY EROSION CONTROLS AND RETAINED SOILS MUST BE REMOVED AND DISPOSED OF PROPERLY, UNLESS NEEDED FOR LONG TERM USE FOLLOWING TERMINATION OF PERMIT COVERAGE. (SECTION 2.2.21)

EROSION & SEDIMENT CONTROL PLAN (ESCP) NOTES

- PRIOR TO ANY GROUND DISTURBANCE ON THE SITE ONE INSPECTION WITH DEQ STAFF IS REQUIRED. ISSUANCE OF THIS PLAN DOES NOT RELIEVE THE PERMIT HOLDER AND/OR THE CONTRACTOR FROM ALL OTHER PERMITTING REQUIREMENTS. PRIOR TO BEGINNING CONSTRUCTION ACTIVITIES. ALL OTHER NECESSARY APPROVALS SHALL BE OBTAINED. THE EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON THE PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE MEASURES SHALL BE UPGRADED AS NEEDED
- FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DOES NOT LEAVE THE SITE. THE IMPLEMENTATION OF THE ESCP AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THE EROSION AND SEDIMENT CONTROL MEASURES IS THE RESPONSIBILITY OF THE PERMIT HOLDER AND/OR THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND ACCEPTED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED IN THE FIELD BY THE ENGINEER PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE PERMIT HOLDER AND/OR THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION. THE EROSION AND SEDIMENT CONTROL MEASURES ON ACTIVE SITES SHALL BE INSPECTED AND MAINTAINED DAILY AND WITHIN THE 24 HOURS AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF RAIN PER 24 HOUR PERIOD. MEASURES SHALL BE INSPECTED BY THE PERMIT HOLDER AND/OR THE CONTRACTOR AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS OR ADJUSTMENTS SHALL BE MADE IMMEDIATELY.
- THE EROSION AND SEDIMENT CONTROL MEASURES ON INACTIVE SITES SHALL BE INSPECTED A MINIMUM OF ONCE EVERY TWO (2) WEEKS OR WITHIN 48 HOURS FOLLOWING A STORM EVENT. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE PROTECTED FROM DAMAGE AT ALL TIMES. CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL PERMANENT RE-VEGETATION HAS BEEN STABILIZED. ANY MEASURE THAT IS DAMAGED OR DESTROYED SHALL BE REPAIRED OR REPLACED IMMEDIATELY. ANY AREAS OF EXPOSED SOILS, INCLUDING ROADWAY EMBANKMENTS, THAT WILL NOT BE DISTURBED FOR TWO DAYS DURING THE WET SEASON (OCTOBER 1 TO APRIL 30) OR SEVEN DAYS DURING THE DRY SEASON (MAY 1 TO
- SEPTEMBER 30) SHALL BE IMMEDIATELY STABILIZED WITH AN APPROVED ESC METHOD (SEEDING & MULCHING WITH STRAW, BARK, COMPOST, OR PLASTIC COVERING, ETC.). STREET SWEEPING SHALL BE PERFORMED AS NEEDED OR WHEN DIRECTED BY THE CITY INSPECTOR TO ENSURE PUBLIC RIGHTS-OF-WAY ARE KEPT CLEAN AND FREE OF DEBRIS. STREET FLUSHING IS PROHIBITED. WHEN TRUCKING SATURATED SOILS FROM THE SITE, EITHER WATER-TIGHT TRUCKS SHALL BE USED OR LOADS SHALL BE DRAINED ON SITE UNTIL DRIPPING HAS BEEN REDUCED TO NO MORE THAN ONE GALLON PER HOUR. SEDIMENT
- LADEN WATER WILL NOT BE ALLOWED TO ENTER THE STORM WATER SYSTEM. EXTRACTED GROUND WATER FROM EXCAVATED TRENCHES SHALL BE DISPOSED OF IN A SUITABLE MANNER WITHOUT DAMAGE TO ADJACENT PROPERTY, CITY'S STORM WATER SYSTEM, WATER FEATURES, AND RELATED NATURAL
- RESOURCES. APPROVAL OF A DEWATERING SYSTEM DOES NOT GUARANTEE THAT IT WILL MEET COMPLIANCE OR BE ACCEPTABLE FOR USE IN ALL SITUATIONS. MODIFICATIONS TO THE DEWATERING SYSTEM WILL BE REQUIRED IF COMPLIANCE CAN NOT BE MET. AT NO TIME WILL SEDIMENT LADEN WATER BE ALLOWED TO LEAVE THE CONSTRUCTION SITE. 11. A SUPPLY OF MATERIALS NECESSARY TO MEET COMPLIANCE AND IMPLEMENT THE ESCP OR OTHER BEST MANAGEMENT EROSION PRACTICES UNDER ALL WEATHER CONDITIONS SHALL BE MAINTAINED AT ALL TIMES ON THE CONSTRUCTION 6.
- 12. NO HAZARDOUS SUBSTANCES, SUCH AS PAINT, THINNERS, FUELS, AND OTHER CHEMICALS SHALL BE RELEASED ONTO THE SITE, ADJACENT PROPERTIES, OR INTO WATER FEATURES, THE CITY'S STORM WATER SYSTEM, OR RELATED RESOURCES. THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED TO ENSURE CONTINUED PROPER FUNCTIONING. WRITTEN RECORDS SHALL BE KEPT OF WEEKLY REVIEWS OF THE ESC FACILITIES DURING THE WET
- SEASON (OCTOBER 1 TO APRIL 30) AND OF MONTHLY REVIEWS DURING THE DRY SEASON (MAY 1 TO SEPTEMBER 30). SAWCUTTING MEASURES

- IF SAWCUTTING, CONTRACTOR SHALL FOLLOW THIS THREE-STEP PROCEDURE TO ELIMINATE DISCHARGE. BLOCK DRAINS, LOCATE ALL NEARBY STORM DRAIN INLETS, CULVERTS, AND CATCH BASINS THROUGH WHICH SLURRY DISCHARGES MAY ENTER A WATERWAY. IF YOU ARE WITHIN ACCESS OF A STORM DRAIN INLET, BLOCK THE PATH TO THE NEAREST DRAIN. EITHER DIVERT FLOWS OR BERM INLETS TO POOL WATER AWAY FROM DRAINS. ANOTHER OPTION IS TO SEAL OR PLUG THE INLET. MINIMIZE SLURRY MOVEMENT. SLURRY AND SEDIMENT FROM SAWCUTTING OPERATIONS SHOULD BE CONFINED TO THE IMMEDIATE WORK AREA BY USING TEMPORARY BERMS OR DIVERSION STRUCTURES. MINIMIZE THE TRACKING OF SLURRY OFF SITE BY CARS AND
- REMOVE SLURRY. EFFICIENTLY AND EFFECTIVELY COLLECT AND REMOVE ALL SLURRY AND RUNOFF FROM THE SAW CUTTING OPERATION AS SOON AS POSSIBLE. BE SURE TO INCLUDE REMOVAL OF ANY SLURRY COLLECTED IN OR NEAR THE STORM DRAIN INLETS BY PUMPING TO A COLLECTION VESSEL OR USING A WET/DRY VACUUM. IT MAY BE NECESSARY TO USE A STREET SWEEPER OR WASH DOWN THE AREA AND COLLECT THE WATER. NO SLURRY OR WASHWATER IS ALLOWED TO DRAIN OFF SITE. SLURRY AND WASH WATER MAY BE DISPOSED OF ON SITE WHERE IT CAN FILTER INTO THE GROUND. OTHERWISE, DISPOSE OF ALL COLLECTED SLURRY AND WASH WATER PROPERLY. ONE WAY IS TO

ALLOW COLLECTED SLURRY TO SETTLE AND DECANT THE WATER ONTO THE GROUND OR, WITH APPROVAL, INTO THE SANITARY SEWER WITH APPROVAL. DISPOSE OF THE SOLIDS APPROPRIATELY WET WEATHER PERMIT CONDITIONS

WET WEATHER EROSION PREVENTION MEASURES WILL BE IN EFFECT FROM OCTOBER 1 THROUGH APRIL 30.

SOIL EXPOSED FOR MORE THAN 2 DAYS SHALL BE COVERED WITH PLASTIC SHEETING, MATTING, OR A 2-INCH LAYER OF MULCH, BARK, WOOD CHIPS, SAWDUST, OR STRAW TO MINIMIZE EROSION POTENTIAL. EXPOSED SOILS SHALL BE SEEDED NO LATER THAN SEPTEMBER 1ST TO ALLOW TIME FOR PROPER GERMINATION AND GROWTH BEFORE THE WET WEATHER SEASON.

ECO.O EROSION CONTROL COVER & NOTES ECO.1 EROSION CONTROL NOTES EC1.0 EROSION CONTROL EXISTING CONDITIONS & DEMO. PLAN EC2.0 EROSION CONTROL SITE PLAN EC3.0 EROSION CONTROL DETAILS

OWNER/APPLICANT

CITY OF HARRISBURG CONTACT: CHUCK SCHULZ 120 SMITH STREET P.O. BOX 378 HARRISBURG, OR 97446 PHONE: (541) 995-6655 E-MAIL: cscholz@ci.harrisburg.org

BMP INSTALLER/MAINTAINER

CONTRACTOR NAME: TBD CONTACT: TBD

RAIN GAUGE LOCATION

STATION "WILLAMETTE RIVER NEAR HARRISBURG" LAT/LONG: 44.2705, -123.1725 APPROXIMATELY .38 MI. EAST OF SITE. (https://waterdata.usgs.gov)

ENGINEER/ESCP PREPARER

BRANCH ENGINEERING, INC. CONTACT: DAMIEN GILBERT, P.E. 310 5th STREET SPRINGFIELD, OREGON 97477 OFFICE: (541) 746-0637 EMAIL: damieng@branchengineering.com

SURVEYOR

VICINITY MAP

BRANCH ENGINEERING, INC. CONTACT: DANIEL NELSON, PLS 310 5th STREET SPRINGFIELD, OREGON 97477 OFFICE: (541) 746-0637 EMAIL: dann@branchengineering.com

CONTRACTOR

CONTRACTOR NAME: TBD CONTACT: TBD ADDRESS: TBD PHONE:

LIST OF SUBCONTRACTORS

TO BE DETERMINED

SITE INFORMATION

TYPF OF DEVELOPMENT: THE PROJECT ADDRESSED BY THIS EROSION AND SEDIMENT CONTROL PLAN CONSISTS OF RECONSTRUCTION OF AN EXISTING ROAD AND SIDEWALK.

- 1. CONSTRUCTION ACTIVITY WILL CONSIST OF:
- CLEARING AND GRADING PAVING UTILITY CONSTRUCTION
- 2. PROJECT TIMELINE: SUMMER, 2024 CL FARING: MASS GRADING: SUMMER, 2024
- UTILITY CONSTRUCTION: SUMMER, 2024 VERTICAL CONSTRUCTION: SUMMER, 2024 SUMMER, 2024 FINAL STABILIZATION:
- PROJECT HOURS: MONDAY-SATURDAY, 7AM-6PM 4. PROJECT SITE AREAS:
- PERCENT OF SITE DISTURBED: 100%

IMPROVEMENT LENGTH:

- 1.03 AC TOTAL ARFA: DISTURBED AREA: 1.03 AC OFFSITE PUBLIC IMPROVEMENT AREA: N/A
- 33D DAYTON SILT LOAM, 0-2% SLOPE 46D HOLCOLM SILT LOAM, 0-3% SLOPE
- - ROUGH GRADING WILL BE NECESSARY TO ACHIEVE PROPOSED GRADES. ANY SUITABLE EXCAVATION MATERIAL WILL BE USED AS FILL IN LOW AREAS.
- FILL SHALL BE STRUCTURAL.
- 7. CUT AND FILL DATA: CUT: 233 CUBIC YARDS FILL: 205 CUBIC YARDS (CONTRACTOR TO VERIFY)

GRADING, STREET AND UTILITY EROSION CONTROL CONSTRUCTION NOTES

- PERMANENT PLANTINGS SHALL BE PER LANDSCAPE PLANS.
- SLOPE TO RECEIVE PERMANENT SEEDED COMPOST SHALL HAVE THE SURFACE ROUGHENED BY MEANS OF TRACK-WALKING OF THE USE OF OTHER APPROVED IMPLEMENTS. SURFACE ROUGHENING IMPROVES SEED BEDDING AND REDUCED RUN-OFF LONG TERM SLOPE STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEFDING WITH SUNMARK NATIVE FC MIX OR APPROVED ALTERNATE TEMPORARY SLOPE STABILIZATION MEASURES SHALL INCLUDE: COVERING EXPOSED SOIL WITH PLASTIC SHEETING, STRAW
- MULCHING, OR OTHER APPROVED MEASURES. STOCKPILED SOIL OR STRIPPING SHALL BE PLACED IN A STABLE LOCATION AND CONFIGURATION. DURING "WET WEATHER' PERIODS, STOCKPILES SHALL BE COVERED WITH PLASTIC SHEETING. SEDIMENT FENCE IS REQUIRED AROUND THE PERIMETER OF THE STOCKPILE. EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THOUGH THE USE OF TEMPORARY SEEDING AND MULCHING, SLOPES EXCEEDING 25% MAY REQUIRE ADDITIONAL EROSION CONTROL MEASURES.
- AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF FINE SPRAY OF WATER, STRAW MULCHING, OR OTHER APPROVED MEASURES. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING MAY BE
- REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT. ACTIVE INLETS TO STORM WATER SYSTEMS SHALL BE PROTECTED THROUGH THE USE OF APPROVED INLET PROTECTION MEASURES, ALL INLET PROTECTION MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED. 10. SATURATED MATERIALS THAT ARE HAULED OFF-SITE MUST BE TRANSPORTED IN WATER-TIGHT TRUCKS TO ELIMINATE SPILLAGI
- OF SEDIMENT AND SEDIMENT-LADEN WATER. AN AREA SHALL BE PROVIDED FOR THE WASHING OUT OF CONCRETE TRUCKS IN A LOCATION THAT DOES NOT PROVIDE RUN-OFF THAT CAN ENTER THE STORM WATER SYSTEM (MINIMUM 50 FEET AWAY FROM STORM FACILITY, NATURAL RESOURCE PROTECTION AREA OR STORM WATER DISCHARGE POINT. IF THE CONCRETE WASH-OUT AREA CAN NOT BE CONSTRUCTED GREATER THAN 50' FROM ANY DISCHARGE POINT, SECONDARY MEASURES SUCH AS BERMS OR TEMPORARY SETTLING PITS MAY BE REQUIRED. THE WASH-OUT SHALL BE LOCATED WITHIN SIX FEET OF TRUCK ACCESS AND BE CLEANED WHEN IT REACHED
- 50% OF THE CAPACITY. 12. SWEEPINGS FROM EXPOSED AGGREGATE CONCRETE SHALL NOT BE TRANSFERRED TO THE STORM WATER SYSTEM. SWEEPINGS SHALL BE PICKED UP AND DISPOSED IN THE TRASH. 13. AVOID PAVING IN WET WEATHER WHEN PAVING CHEMICALS CAN RUN-OFF IN TO THE STORM WATER SYSTEM.
- 14. COVER CATCH BASINS, MANHOLES, AND OTHER DISCHARGE POINTS WHEN APPLYING SEAL COAT, TACK COAT, ETC. TO PREVENT INTRODUCING THESE MATERIALS TO THE STORM WATER SYSTEM.

civil • transportation structural • geotechnical SURVEYING

310 5th Street Springfield, OR 97477

p: 541.746.0637 www.BranchEngineering.com



SCALE: 1"=2000

project title:

SNSLING

S

ST/JL

MAY 7, 2024

23-009A **EROSION** CONTROL

COVER SHEET

SPILL RESPONSE

CONTRACTOR SHALL HAVE SPILL KITS AT THE PROJECT SITE AT ALL TIMES. THERE SHALL BE SIGNAGE MOUNTED IN APPROPRIATE LOCATIONS STATING "SPILL KIT INSIDE." CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE SPILL KITS AND TRAINING EMPLOYEES ON HOW TO USE THEM.

- IN THE EVENT OF A SPILL, CONTRACTOR SHALL PROCEDE AS FOLLOWS:
- DETERMINE TYPE OF SPILL, AND BEST ACTION TO REMOVE SPILL • IF SPILL IS TOO LARGE TO CONTAIN, OR CLEAN, CALL EMERGENCY SERVICES (911, OR EMERGENCY CLEAN-UP TEAMS SUCH AS NORTHWEST HAZMAT, OR ENVIRONMENTAL CONTROL)
- CONTAIN SPILL CLEAN AND DISPOSE OF SPILL

ONCE ALL SUBCONTRACTORS ARE UNDER CONTRACT, GENERAL CONTRACTOR SHALL PROVIDE A FULL LIST OF POLLUTANTS THEY WILL HAVE ONSITE. THIS LIST SHALL BE KEPT ON SITE WITH THE GENERAL CONTRACTOR.

NOTES

1. ENTIRE LIMITS OF DISTURBANCE MAY BE SUBJECTED TO POLLUTANTS, & EQUIPMENT TRAFFIC. CONTRACTOR SHALL BE RESPONSIBLE FOR MANAGING SITE AND ANY POTENTIAL POLLUTANT DISCHARGE.

PROJECT SITE CONTRACTOR LIST

CONTRACTOR COMPANY NAME	CLEARING	MASS GRADING/ UTILITY CONSTRUCTION/ VERTICAL CONSTRUCTION	FINAL STABILIZATION
GENERAL:			
TBD	X	Χ	Х
SUBCONTRACTORS:			
NOT APPLICABLE AT THIS TIME			

THIS PLAN SHEET WAS SETUP FOR CONTRACTOR USE AS NEEDED TO AID IN MAINTAINING ACTIVE SUBCONTRACTOR AND POLLUTANT LISTS AND IS SEPARATE FROM THE CIVIL

CONTRACTOR TO ADD TO EROSION AND SEDIMENT CONTROL SITE PLAN: 1. ACTIVE LIST OF LOCATIONS OF POLLUTANTS

- 2. PORTA POTTY LOCATIONS
- 3. WASTE RECEPTACLES
- 4. WHERE FERTILIZER WILL BE USED

NOTE: CONTRACTOR IS REQUIRED TO MAINTAIN ACTIVE LIST OF SUBCONTRACTORS AND POLLUTANTS USED THROUGH THE COURSE OF THE PROJECT ALONG WITH THEIR STORAGE LOCATION ON SITE AT ALL TIMES. CONTRACTOR TO SUPPLY THE ACTIVE LIST TO THE DEQ

PROJECT SITE POLLUTANT LIST MATRIX

	POTENTIAL POLLUTANT	POLLUTANT ACTIVITY	PROJECT LOCATION	CONTRACTOR	NOTES
1	DIESEL FUEL	EXCAVATION / MOVING MATERIALS	ENTIRE PROJECT	TBD	
2	GASOLINE FUEL	EXCAVATION / MOVING MATERIALS	ENTIRE PROJECT	TBD	
3	MOTOR OIL, HYDRAULIC OIL	EXCAVATION / MOVING MATERIALS / HEAVY EQUIPMENT	ENTIRE PROJECT	TBD	
4	ANTIFREEZE COOLANT	HEAVY EQUIPMENT	ENTIRE PROJECT	TBD	
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					

structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477

civil • transportation

p: 541.746.0637 www.BranchEngineering.com



project title:

ш

Š


KENSLING

MAY 7, 2024

23-009A

EROSION CONTROL NOTES


EC0.1



- INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
- 2. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE LIMITS OF DISTURBANCE.
- 3. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING, MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE
- 4. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING FOR THE DURATION OF THE PROJECT, RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: CHECK DAMS, SURFACE ROUGHENING AND BANK STABILIZATION.
- 5. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
- 6. CONTRACTOR SHALL COORDINATE WITH EPSC CERTIFIED VISUAL MONITORING INSPECTOR TO DETERMINE FINAL BMP TYPE AND PLACEMENT.
- 7. CONSTRUCTION WILL OCCUR DURING SUMMER MONTHS. DEWATERING IS NOT EXPECTED TO OCCUR. IF DEWATERING IS REQUIRED, DISCHARGE WATER TO ESTABLISHED VEGETATION IN UPLAND AREA.

EROSION CONTROL KEYNOTES

- CONSTRUCT SEDIMENT FENCE AND/OR COMPOST FILTER SOCK AT LIMITS OF DISTURBANCE WHERE NECESSARY TO LIMIT SEDIMENT DRAINING ONTO PRIVATE PROPERTY. CONTRACTOR TO COORDINATE WITH EPSC CERTIFIED VISUAL MONITORING INSPECTOR FOR FINAL PLACEMENT. INSTALLATION OF BMPS PER OREGON STANDARD DRAWINGS RD1040, SHEET EC3.0.
- USE EXISTING PAVED ROAD AS CONSTRUCTION ENTRANCE/EXIT.
- INSTALL TYPE 7 INLET PROTECTION FOR CURB INLET PER OREGON STANDARD DRAWING RD1010 ON SHEET EC3.0.
- INSTALL TYPE 10 INLET PROTECTION FOR CATCH BASIN PER OREGON STANDARD DRAWING RD1010 ON SHEET EC3.0.
- PROVIDE DUMPSTER CONTAINERS FOR CONSTRUCTION DEBRIS. FINAL LOCATION TBD BY CONTRACTOR.
- TEMPORARY STOCKPILE LOCATION. INSTALL PLASTIC SHEETING ON STOCKPILE PER ODOT TECHNICAL SERVICES DETAIL DET6001 ON SHEET EC3.0. CONTRACTOR SHALL COORDINATE LOCATION WITH INSPECTOR PRIOR TO INSTALLATION.
- SAWCUT AS NEEDED AND REMOVE EXISTING PAVEMENT. ENSURE THAT NO CONTAMINANTS RESULTING FROM SAWCUTTING ACTIVITIES ENTER THE STORMWATER SYSTEM.
- TEMPORARY AREA FOR EQUIPMENT STORAGE & MAINTENANCE, MATERIAL STORAGE, STAGING, FUEL STORAGE & REFUELING, AND HAZARDOUS WASTE. SEE SPILL PREVENTION AND CONTROL NOTES ON SHEET ECO.1.
- DURING STORM EVENTS, INSTALL WATTLE ON DRIVEWAYS AND PEDESTRIAN ACCESSES, AS SHOWN, TO CONTROL RUN OFF. PLACE A SANDBAG AT EACH END OF WATTLE AND 3' OC TO HOLD IT IN PLACE. REMOVE FOR VEHICULAR TRAFFIC WHEN NEEDED.



structural • geotechnical SURVEYING 310 5th Street Springfield, OR 97477

civil • transportation

p: 541.746.0637 www.BranchEngineering.com



Expires: June 30, 2025

project title:

TREE S KENSLING T TC STREI ORE SMIT! ISBUR(

ي بيا

FROM HARRI

revisions:

_____ EXISTING CONTOUR

SEDIMENT FENCE, OR APPROVED ALTERNATE.

DIRECTION OF FLOW

DECIDUOUS TREE

EVERGREEN TREE


STOCKPILE AREA

TREE TO BE REMOVED

EQUIPMENT AND MATERIAL AREA

MAY 7, 2024 drawn by: ST/JL designer:

23-009A **EROSION CONTROL EXISTING COND**



- 1. ALL BASE ESC MEASURES MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
- 2. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER (PERIMETER SEDIMENT FENCE).
- 3. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING, MAY BE REQUIRED TO INSURE THAT
- 4. STOCKPILED SOIL OR STRIPPINGS SHALL BE PLACED IN A STABLE LOCATION AND CONFIGURATION. STOCKPILES SHALL BE
- 5. EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THROUGH THE USE OF TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS OR MATS, MID-SLOPE SEDIMENT FENCES OR WATTLES, OR OTHER APPROPRIATE MEASURES.
- 6. AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES
- KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- 8. ACTIVE INLETS TO STORM WATER SYSTEMS SHALL BE PROTECTED THROUGH THE USE OF APPROVED INLET PROTECTION MEASURES. ALL INLET PROTECTION MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED AS NEEDED.
- 9. SATURATED MATERIALS THAT ARE HAULED OFF-SITE MUST BE TRANSPORTED IN WATER-TIGHT TRUCKS TO ELIMINATE SPILLAGE OF SEDIMENT AND SEDIMENT-LADEN WATER.
- 10. AN AREA SHALL BE PROVIDED FOR THE WASHING OUT OF CONCRETE TRUCKS IN A LOCATION THAT DOES NOT PROVIDE RUN-OFF THAT CAN ENTER THE STORM WATER SYSTEM. IF THE CONCRETE WASH-OUT AREA CAN NOT BE CONSTRUCTED GREATER THAN 50' FROM ANY DISCHARGE POINT, SECONDARY MEASURES SUCH AS BERMS OR TEMPORARY SETTLING PITS MAY BE REQUIRED. THE WASH-OUT SHALL BE LOCATED WITHIN SIX FEET OF TRUCK ACCESS AND BE CLEANED WHEN IT REACHES 50% OF THE CAPACITY.
- 11. SWEEPINGS FROM EXPOSED AGGREGATE CONCRETE SHALL NOT BE TRANSFERRED TO THE STORM WATER SYSTEM. SWEEPINGS SHALL BE PICKED UP AND DISPOSED IN THE TRASH.
- 12. AVOID PAVING IN WET WEATHER WHEN PAVING CHEMICALS CAN RUN-OFF INTO THE STORM WATER SYSTEM.

DISCHARGE WATER TO ESTABLISHED VEGETATION IN UPLAND AREA.

copyright © 2016 Branch Engineering, Inc.


- 13. USE BMPs SUCH AS CHECK-DAMS, BERMS, AND INLET PROTECTION TO PREVENT RUN-OFF FROM REACHING DISCHARGE POINTS.
- 14. COVER CATCH BASINS, MANHOLES, AND OTHER DISCHARGE POINTS WHEN APPLYING SEAL COAT, TACK COAT, ETC. TO PREVENT INTRODUCING THESE MATERIALS TO THE STORM WATER SYSTEM.

15. ROUTINE MAINTENANCE SPECIFICATIONS FOR PERIMETER CONTROLS DOCUMENTED IN THE EPSCP MUST INCLUDE SECTIONS 2.1.4,

- 2.1.5 AND 2.2.6 OF THE GENERAL PERMIT NPDES CONSTRUCTION STORMWATER DISCHARGE PERMIT. 16. CONTRACTOR SHALL COORDINATE WITH EPSC CERTIFIED VISUAL MONITORING INSPECTOR TO DETERMINE FINAL BMP TYPE AND
- PLACEMENT. 17. CONSTRUCTION WILL OCCUR DURING SUMMER MONTHS. DEWATERING IS NOT EXPECTED TO OCCUR. IF DEWATERING IS REQUIRED,

EROSION CONTROL KEYNOTES

- CONSTRUCT SEDIMENT FENCE AND/OR COMPOST FILTER SOCK AT LIMITS OF DISTURBANCE WHERE NECESSARY TO LIMIT SEDIMENT DRAINING ONTO PRIVATE PROPERTY. CONTRACTOR TO COORDINATE WITH EPSC CERTIFIED VISUAL MONITORING INSPECTOR FOR FINAL PLACEMENT. INSTALLATION OF BMPS PER OREGON STANDARD DRAWINGS RD1040, SHEET EC3.0.
- USE EXISTING PAVED ROAD AS CONSTRUCTION ENTRANCE/EXIT.
- INSTALL TYPE 7 INLET PROTECTION FOR CURB INLET PER OREGON STANDARD DRAWING RD1010,
- INSTALL TYPE 10 INLET PROTECTION FOR CATCH BASIN PER OREGON STANDARD DRAWING RD1010, SHEET EC3.0.
- PROVIDE DUMPSTER CONTAINERS FOR CONSTRUCTION DEBRIS. FINAL LOCATION TBD BY CONTRACTOR.
- TEMPORARY STOCKPILE LOCATION. INSTALL PLASTIC SHEETING ON STOCKPILE PER ODOT TECHNICAL SERVICES DETAIL DET6001 ON SHEET EC3.0. CONTRACTOR SHALL COORDINATE LOCATION WITH INSPECTOR PRIOR TO INSTALLATION.
- TEMPORARY AREA FOR EQUIPMENT STORAGE & MAINTENANCE, MATERIAL STORAGE, STAGING, FUEL STORAGE & REFUELING, AND HAZARDOUS WASTE. SEE SPILL PREVENTION AND CONTROL NOTES ON SHEET ECOOO.
- DURING STORM EVENTS, INSTALL WATTLE ON DRIVEWAYS AND PEDESTRIAN ACCESSES, AS SHOWN, TO CONTROL RUN OFF. PLACE A SANDBAG AT EACH END OF WATTLE AND 3' OC TO HOLD IT IN PLACE. REMOVE FOR VEHICULAR TRAFFIC WHEN NEEDED.



LEGEND

LIMITS OF DISTURBANCE _ _ _ - -180- _ _ _ EXISTING CONTOUR SEDIMENT FENCE, OR APPROVED ALTERNATE. DIRECTION OF FLOW DECIDUOUS TREE EVERGREEN TREE TREE TO BE REMOVED

STOCKPILE AREA

EQUIPMENT AND MATERIAL AREA

revisions:

KENSLING

ЫÜ

STREI ORE

MIT

S

OM

ENGINEERING

civil • transportation

structural • geotechnical

SURVEYING 310 5th Street Springfield, OR 97477 p: 541.746.0637 www.BranchEngineering.com


Expires: June 30, 2025


project title:


MAY 7, 2024 designer

ST/JL 23-009A **EROSION**

CONTROL PROPOSED







HARRISBURG 6TH STREET RECONSTRUCT

civil • transportation

structural • geotechnical

SURVEYING

310 5th Street

Springfield, OR 97477

p: 541.746.0637

www.BranchEngineering.com

√`#62780PE^か

DIGITALLY SIGNED

OREGON

Expires: June 30, 2025

RE

S

KENSLING

STREET TO OREGON

FROM SMITH SHARISBURG,

project title:

EC3.0

MAY 7, 2024

EROSION

CONTROL

DETAILS

ST/JL

23-009A